



Bulk Density: 2.77 gm/cc

BH.No.	Section Line	Sectional Area (m ²)	Strike Influence (m)	Volume (m ³)	Geological Gross In-situ Resources (tonnes)	Average Quality									
						CaO %	MgO %	Al ₂ O ₃ %	SiO ₂ %	Fe ₂ O ₃ %	SO ₃ %	P ₂ O ₅ %	K ₂ O %	Na ₂ O %	LOI %
MDK-04	S1-S1'	13200.00	800	10560000.00	29251200.00	45.01	3.02	2.71	9.11	0.74	0.14	0.05	0.56	0.05	38.31
MDK-04	S1-S1'	7530.26	800	6024207.04	16687053.50	45.95	4.94	1.31	4.93	0.35	0.32	0.02	0.26	0.04	41.67
MDK-05	S2-S2'	10740.00	800	8592000.00	23799840.00	47.13	2.86	1.96	6.52	0.56	0.29	0.05	0.43	0.04	39.87
MDK-05	S2-S2'	7609.11	800	6087288.24	16861788.42	47.10	4.58	1.15	4.25	0.29	0.44	0.02	0.23	0.05	41.66
Total Geological Gross In-situ Resources of Cement Grade Limestone in Tonnes					86599881.93	45.96	3.42	2.12	7.23	0.59	0.23	0.04	0.44	0.04	39.65
Total Geological Gross In-situ Resources of Cement Grade Limestone in Million Tonnes (MT)					86.60										