

OVERBURDEN (O.B) AND INTER-BURDEN (I.B) TO MINERAL RATIO, SIMAR BLOCK

Serial Number	Borehole Name	Overburden (OB) (m)	Total OB	Mineralize Zone Thickness (m)				Inter-burden Thickness (m)				Total Overburden (OB+IB) (m)	Overburden: Mineralized Zone Thickness
				From	To	Thickness	Total Thickness	From	To	Thickness	Total Inter-burden Thickness		
1	SBH-1	0.15	0.15	0.15	5.68	5.53	5.53	–	–	–	–	0.15	0.03
2	SBH-2	1.48	1.48	1.48	4.24	2.76	2.96	4.24	7.00	2.76	2.76	4.24	1.43
				7.00	7.20	0.20		–	–	–			
3	SBH-3	–	–	–	–	–	–	–	–	–	–	–	–
4	SBH-4	6.00	6.00	6.00	10.00	4.00	4.00	–	–	–	–	6.00	1.50
												Average Overburden: Mineralized Zone	0.99