

**Details of Borehole wise tungsten (W) Zones demarcated at 400 PPM W cut-off in
Murara-Devendrapura Block (G-3), District-Niwari, Madhya Pradesh**

Borehole. No.	Intersection Depth (M)		Thickness (m)	W	Sn	Cu	Pb	Zn
	From	To		Calculated weighted average grade in PPM(DL=1PPM)				
MMDB-02	61.42	62.39	0.97	494.30	4.63	23.52	2.91	9.23
	79.62	90.90	11.28	463.98	45.92	17.19	3.23	5.66
	102.00	107.52	5.52	443.05	<1	7.62	11.97	1.15
	111.00	111.69	0.69	478.73	<1	10.87	6.94	5.08
MMDB-03	45.00	46.02	1.02	428.11	<1	11.83	<1	1.73
	59.27	68.67	9.40	405.46	<1	11.78	27.92	2.59
	74.05	76.25	2.20	429.34	<1	8.20	8.07	10.93
	81.55	82.70	1.15	521.40	<1	12.12	5.52	4.41
	86.83	89.40	2.57	478.74	<1	15.26	6.01	<1
	101.00	102.00	1.00	403.48	<1	12.61	1.74	<1
	102.99	119.00	16.01	402.05	<1	14.54	8.35	6.84
MMDB-04	54.92	61.01	6.09	467.90	<1	4.27	2.04	1.50
	65.99	75.02	9.03	398.83	<1	13.61	17.53	4.25
	80.98	81.98	1.00	452.25	<1	3.61	3.18	5.03
MMDB-08	81.91	84.73	2.82	397.84	<1	2.59	20.86	5.58
	137.40	138.33	0.93	411.60	2.97	20.60	10.40	73.76
	142.15	143.10	0.95	440.66	4.82	1.72	2.76	0.90
MMDB-09	57.56	58.46	0.90	409.63	1.04	13.53	16.13	24.55
	80.00	80.75	0.75	504.54	<1	180.93	282.51	1.09
	82.28	82.75	0.47	471.38	<1	15.52	43.24	10.66
	117.32	119.33	2.01	509.43	<1	25.83	50.44	11.75
MMDB-11	39.75	40.72	0.97	438.39	<1	18.98	3.37	<1
	71.00	72.00	1.00	416.40	<1	8.61	<1	<1
	78.00	79.00	1.00	425.73	<1	2.93	1.37	<1
	82.05	83.03	0.98	422.14	<1	10.03	3.99	<1