

Statement showing section wise resource estimated by geological cross section method at 400ppm W cut-off and minimum stopping width of 2m in Murara-Devendrapura Block (G-3), District-Niwari, Madhya Pradesh

Section -wise Resource of Murara Sub block				
Section No.	Inferred Resource (Tons)	Total Resource (Tons)	Resource (%)	Weighted average grade of W in PPM
S2-S2'	304337.030	304337.030	29.52	457.10
S3-S3'	535294.578	535294.578	51.93	411.54
S4-S4'	191237.682	191237.682	18.55	426.41
Total:	1030869.290	1030869.290	100	427.75
Resource in Million tonnes (Murara-Sub Block)		1.031		427.75
Section -wise Resource of Devendrapura Sub block				
Section No.	Inferred Resource (Tons)	Total Resource (Tons)	Resource (%)	Weighted average grade of W in PPM
S9-S9'	54106.759	54106.759	50.36	397.84
S10-S10'	53334.051	53334.051	49.64	509.43
Total	107440.810	107440.810	100	453.23
Resource in Million tonnes (Devendrapura-Sub Block)		0.107		453.23
Total Combined Resources (G3) of Murara and Devendrapura Sub Blocks (i.e Murara-Devendrapura Block) in million tonnes (MT)		1.138		430.16