

ANNEXURE-2													
OVERBURDEN (O.B) AND INTER-BURDEN (I.B) TO MINERAL RATIO, LODHVA BLOCK													
Serial Number	Borehole Name	Overburden (OB) (m)	Total OB	Mineralize Zone Thickness (m)				Inter-burden Thickness (m)				Total Overburden (OB+IB) (m)	Overburden: Mineralized Zone Thickness
				From	To	Thickness	Total Thickness	From	To	Thickness	Total Inter-burden Thickness		
1	LBH-1	0.35	0.35	0.35	6.40	6.05	6.05	—	—	—	—	0.35	0.06
2	LBH-2	0.13	0.13	0.13	5.52	5.39	8.96	5.52	14.50	8.98	10.06	10.19	1.14
				14.50	16.64	2.14		16.64	17.72	1.08			
				17.72	19.15	1.43		—	—	—			
3	LBH-3	0.30	0.30	0.30	4.50	4.20	4.20	—	—	—	—	0.30	0.07
4	LBH-4	0.50	0.50	0.50	11.50	11.00	11.00	—	—	—	—	0.50	0.05
5	LBH-5	0.26	0.26	0.26	7.00	6.74	8.69	7.00	11.40	4.40	4.40	4.66	0.54
				11.40	13.35	1.95		—	—	—			
6	LBH-6	0.26	0.26	0.26	7.00	6.74	6.74	—	—	—	—	0.26	0.04
7	LBH-7	0.15	0.15	0.15	7.40	7.25	8.45	7.40	8.50	1.10	1.10	1.25	0.15
				8.50	9.70	1.20		—	—	—			
												Average Overburden: Mineralized Zone	0.29